No.	Items of work	Per	Quantity	Total
10	Rates for masonry cisterns as in Branch A and quantities as in A	To be given individually		
11	Rates for branch connections including laying and jointing.			
	(*a*) 4″ Lead joints	Each	20	
	(*b*) 3″ Lead joints	,,	20	
	(*c*) 2½″ Lead joints	,,	20	
12	Removing and resetting drain slabs in mortar ..	S.ft.	50	
13	Dismantling and constructing masonry	C.ft.	100	
14	Carting surplus materials back to Stores	Cwt. mile		

V. GANESHA IYER,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 17th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 10th February 1936, for the work of constructing a pump and filter house for water supply to Mandya Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by 31st March 1936.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 140 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for the work of constructing a pump and filter house for water supply to Mandya Town " in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work of constructing a pump and filter house for water supply to Mandya Town.

Sl. No.	Particulars	Unit	Quantity
1	Earthwork excavation for foundation and filling in the basement (hard gravel)	C.yd.	27
2	Concrete broken stone jelly in chunam mortar	C.ft.	298
3	Burnt stone in clay with corners squared and dressed	,,	592
4	Burnt brick in clay	,,	642
5	Burnt brick in chunam mortar	,,	376
6	Burnt stone slabs 6″ thick, dressed and fixed in mortar	S.ft.	181
7	Dressing the stone slabs 2 lines	,,	78
8	Reinforced cement concrete slabs	C.ft.	27
9	Teakwood wrought and put up including wood oiling 2 coats ..	,,	56·54
10	Teakwood battened door with 5″×6″ frame and 1½″ thick shutter four fold as per design with the necessary clamps and fittings, etc., complete including painting with 2 coats of silicate paint	S.ft.	86
11	Teakwood windows 1½″ thick glazed shutters and top portion fitted with expanded metal (as per design) including ¾″ diameter round iron bars and necessary clamps and fittings, etc., complete together with 2 coats of paint	,,	221
12	Roofing with 1st class Mangalore Tiles on 2″×1″ Teakwood reepers including wood oiling, etc., complete	Sqr.	5·96
13	Mangalore ridge tiles set in cement mortar	R.ft.	67
14	Reinforced cement concrete roofing 4″ thick	Sqr.	·72
15	Patty cornice 9″ thick (as per design) with burnt brick in chunam including, plastering, etc., complete	R.ft.	100
16	(*a*) Constructing parapet wall about 3′ height with burnt brick in chunam and plastering, etc., complete as per design	R.ft.	22
	(*b*) Do 1½′ high	,,	95
17	Providing ornamental teakwood railings including painting, etc., complete as per design	,,	5
18	Making "U" shaped drains over the roof of the main building behind parapet as per design with cement concrete and plastering, etc., complete	R.ft.	95
19	Providing G. I. rain godown pipes	,,	30
20	Plastering with chunam mortar	Sqr.	24·05
21	Cement pointing to basement	,,	1·93
22	Flooring with 3″ lime concrete, 1″ cement concrete and ½″ cement plaster with a specified colour including cutting tiles, etc. ..	,,	5·43
23	White and colour washing, 2 coats	,,	24·05
24	Teakwood finials	Each	2

B. R. GARUDACHAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 25th January 1936.

The attention of the public is invited to the Notification calling for tenders for constructing a building for the Aryabalika Patasala, Bangalore, on pages 129-131 of Part VI of the *Mysore Gazette*, dated 30th January 1936.

The last date of receiving tenders is 12th February 1936.

Abstract Notification dated 25th January 1936.

The attention of the public is invited to the Notification calling for tenders for constructing a building for the Co-operative Society at Mysore Lancers at Hebbal, Bangalore, on pages 131-132 of Part VI of the *Mysore Gazette*, dated 30th January 1936.

The last date of receiving tenders is 13th February 1936.